

CITY OF BOYNTON BEACH RAW WATER MAIN-SECTION C BOYNTON BEACH, FLORIDA



Project Description

This project consisted of three 42" dia. directional drills:

- 2,520 LF (30' deep) of 42" horizontal directional drill under Woolbright Rd.
- 2,250 LF (20' deep) of 42" horizontal directional drill under Canal and Woolbright Rd.
- 1,350 LF (50' deep) of 42" horizontal directional drill under Interstate I-95

Additionally, this project included 130 LF of 54" casing, jack and bore under CSXR with live pedestrian traffic and CSX cargo and 3000 LF of 36" DIP-open cut utilizing the Felco Conveyor System while only closing one lane of traffic during open excavation

At a Glance

Contract Amount:
\$6.4 Million

Notice to Proceed:
October 30, 2015

Completion Date:
February 25, 2017

Owner:
City of Boynton Beach

Engineer:
Globaltech, Inc.