

# CITY OF BOYNTON BEACH RAW WATER MAIN-SECTION C BOYNTON BEACH, FLORIDA



## Project Description

This project consists of three 42" dia. directional drills:

- 2,520 LF (30' deep) of 42" horizontal directional drill under Woolbright Rd.
- 2,250 LF (20' deep) of 42" horizontal directional drill under Canal and Woolbright Rd.
- 1,350 LF (50' deep) of 42" horizontal directional drill under Interstate I-95

Additionally, this project includes 130 LF of 54" casing, jack and bore under CSXR with live pedestrian traffic and CSX cargo and 3000 LF of 36" DIP-open cut utilizing the Felco Conveyor System while only closing one lane of traffic during open excavation

## At a Glance

**Contract Amount:**  
\$6.4 Million

**Notice to Proceed:**  
October 30, 2015

**Completion Date:**  
February 25, 2017

**Owner:**  
City of Boynton Beach

**Engineer:**  
Globaltech, Inc.