

CITY OF WINSTON-SALEM
SOUTH FORK SEWER IMPROVEMENTS
WINSTON-SALEM, NORTH CAROLINA



Project Description

This project made improvements to the South Fork sewer. It included furnishing, installing and placing into successful operation approximately 6,640 LF of 42" diameter installed at 10' or greater and 2,240 LF of 18"/15" diameter gravity outfall replacement sewer with manholes and connections, removal and disposal of existing outfall sewer pipe and manholes, open cut installation beneath a railroad bridge, temporary bypass pumping at 15 MGD, concrete diversion structure, demolition of existing concrete utility structures, permanent and temporary culverts, erosion control measures, site restoration, and other related work.

At a Glance

Contract Amount:
\$3.5 M

Notice to Proceed:
July 1, 2016

Completion Date:
April 21, 2017

Owner:
City/County of Utility Commission

Engineer:
Hazen and Sawyer