

YORK COUNTY
NEW HERITAGE WASTEWATER PUMP STATION
YORK CO, SOUTH CAROLINA



Project Description

Construction of approximately 1,900 LF of 8" to 24" PVC SDR 26 Gravity Sewer; 15,000 LF 20" DIP Force Main; a 6 MGD submersible wastewater pump station with cast-in place wet well, concrete block control building, odor control unit and generator. Demolition of three existing wastewater pump stations. We also installed 60' diameter, 48' deep sheet pile shoring system supplemented with a soil nail, wire mesh shoring system below the pile tips.

At a Glance

Contract Amount:
\$7.7 M

Notice to Proceed:
August 28, 2015

Completion Date:
June 13, 2017

MGD:
6

Owner:
York County

Engineer:
HDR