

CITY OF HOLLYWOOD
EMERGENCY REPAIRS
HOLLYWOOD, FLORIDA



Project Description

The City of Hollywood was made aware of damages to an existing 60-inch ocean outfall pipeline inside a residential neighborhood. The damages were caused by a directional driller. The City selected Reynolds Construction based on our capability to handle PCCP emergency repairs.

Work included effluent bypass with 48" HDPE. 60" Linestops were required for the bypass. Reynolds completed (2) separate 60" PCCP repairs utilizing 60" closure kits and 60" repair clamps. The repair locations required constant dewatering. We utilized 6" dewatering pumps, discharge into a 8,000gal sedimentation tank, followed by a large silt bag which discharged into a detention pond.

At a Glance

Contract Amount:
\$1.2 M

Notice to Proceed:
May 8, 2018

Completion Date:
August 31, 2018

Owner:
City of Hollywood